PG&E's Approach to Calculating MAOP

MAOP Validation and Class Location Workshop

Vincent Tanguay

Manager, IM Data Delivery & Analysis PG&E

May 12, 2015





- Company Overview
- ☐ Use of 49 CFR § 192.619 (for pipelines above 60 psi)
- ☐ Establishing design MAOP when features are unknown
- □ Role and use of pressure testing
- ☐ Final Remarks

*Company Overview

- Pacific Gas and Electric Company is one of the largest combination natural gas and electric utilities in the United States.
- ➤ The company provides <u>natural gas</u> and <u>electric service</u> to approximately 15 million people throughout a 70,000-square-mile service area in northern and central California.
- Service area stretches from Eureka in the north to Bakersfield in the south, and from the Pacific Ocean in the west to the Sierra Nevada in the east.
- Approximately 6,750 miles of pipelines operating above 60 psi (scope of MAOP Validation).
- ➤ More than 42,000 miles of gas pipelines.
- > 5.1 million electric customer accounts.
- 4.3 million gas customer accounts.



California Requirements

Public Utilities Code 958 requires:

- Test or replacement of untested transmission pipelines
- Engineering-based assumptions may be used to determine Maximum Allowable Operating Pressure (MAOP) as an interim measure

A strength test validates the MAOP.

PG&E's approach is more conservative than these requirements.

MAOP Validation

PG&E uses <u>only</u> 49 CFR 192.619(a) and D.11-06-017 to validate MAOP → Lowest of:

- 619(a)(1): Design pressure of weakest element
- 619(a)(2): Strength test pressure divided by strength test factor (test-supported pressure)
- 619(a)(3): Highest actual operating pressure between 1965 and 1970 (historical pressure)
- 619(a)(4): Maximum safe pressure

PG&E no longer relies on the "Grandfather Clause" 49 CFR 192.619(c)

Design Pressure

49 CFR 192.619(a)(1)

- 49 CFR 192.105: Design formula $P = (2 S t/D) \times F \times E \times T$
- 49 CFR 192.111: Design factor (*F*)
- 49 CFR 192.115: Temperature derating factor (T)
- D.11-06-017: Use combination of historical records and conservative engineering assumptions for D, S, t and long seam type (E) in accordance with PUC 958

Test-Supported Pressure

49 CFR 619(a)(2):


 $MAOP ext{ of } Test = P_T / STF$

- Strength test factor (STF) most stringent requirement of following historical requirements (at the time of the test):
 - Federal code 49 CFR
 - State code (GO 112)
 - PG&E standards


Historical MAOP

49 CFR 192.619(a)(3)


- PG&E did not use MAOP Validation effort to increase pressure beyond historical MAOP (MAOP of Record)
- MAOP of Record obtained from PG&E's MAOP catalog (created in 1979 the catalog kept track of pipeline MAOPs, included and described in March 15, 2011 filing)




MAOP Validation Report



MAOP Validation Report





Requirements to Operate "One Class Out"

- Strength test meets 192.611 requirements (8h, appropriate strength test factor, etc.)
- Not uprated to be one class out

192.607

- One class out in 1970
- Tested in or before 1974

OR

192.611

- Installed in class (or in class in 1970)
- Class location increased after 1970

Recent "One Class Out" Study

Reviewed all features operating one class out

Determined historical class location (parcel data, historical photography, field investigations, etc.)

- At time of install (if installed post-1970)
- In 1970 (if installed pre-1970)

"One Class Out" Study Results

4 categories of findings

- Feature operates one class out since 1970 (49 CFR 192.607)
- Feature operates one class out since class location change per 192.611 (post 7/1/1973)
- Feature installed out of class post 1970 (selfreported - October 9, 2014)
- Feature uprated to be out of class (self-reported -October 9, 2014)

Details of Self-Report October 9, 2014

Installed out of class

Example: Pipeline designed for class 1 location (72% SMYS). Analysis shows that at the time of install, there were more than 10 structures intended for human occupancy. Even if test meets requirements of 49 CFR 192.611, there was never a class location change.

Uprated to be out of class: 49 CFR 192.553(d)

 Example: Pipeline operated in class and was uprated (with test that meets 49 CFR 192.611 requirements) to be one class out.

Standardized Conservative Assumptions (Design Pressure)

Procedure for Resolution of Unknown Pipeline Features (PRUPF) TD-4199P-01

- Assumptions driven by diameter and purchase date (and other specs if known)
- Historical purchase practices
- Most conservative value based on PFL data
 - Was revised as more data was available
- Does not apply to acquired/purchased pipelines

Example: Determine SMYS

For 24" OD, SMLS pipe purchased in 1956

Nominal Pipe Size (inches)	Seam Type & Joint Factor	PURCHASE DATE See Section 3 if Purchase Date is Unknown											
		Un- known Date	Prior to	to	to	to	to	to	to	to	02/28/1995 to 10/18/1998	As of 10/19/1998	
		MINIMUM SMYS of MATERIAL (kpsi)											
24	Un- known	33 SSAW/AOS			35 SMLS/DSAW						42 S/D	35 S/D	
	SSAW / AOS 0.8	33	33	33	N/A								
	SMLS 1.0	30	30	30	35	35	35	35	35	35	42	35	
	DSAW 1.0	35	35	35	35	42	35	35	42	42	42	42	

Assume 35 ksi SMYS

Acquired/Purchased Pipelines

- PG&E standards and historical purchase practices do not apply to pipelines acquired from other operators
- Did not apply PG&E's historical purchase practices pipeline
- Used minimum values when possible
 - Federal minimum SMYS = 24 ksi (per 192.107)
 - Minimum joint factor (0.6 and 0.8 based on diameter, per 192.113)
 - Minimum commercially available wall thickness (WT)

Field Investigations

- Performed inspections on features when conservative assumptions could not validate MAOP
- Effort was made to excavate in strategic locations to expose as many features as possible
- Performed full inspections (OD, WT, long seam characterization, non-destructive testing for yield strength, etc.)
- Continuing to gather field data through various activities (ILI, DA, strength tests, etc.) and using it to validate records and conservative assumptions

Destructive Testing

Use destructive testing to validate assumed SMYS


Example, A.O. Smith SMYS assumed to be 33,000 psi

Recent tests show assumption is conservative

Location	Date	Weld Metal Yield Strength (psi)	Parent Metal Yield Strength (psi)	Reference Number	
Line 147 MP 2.2	8/19/2013	42,900	39,300	5004.9237	
Line 101 MP 12.50	2/9/2015	40,200	42,100	5005.1310	
Line 101 MP 12.63	4/8/2015	45,700	40,000	5005.1566	




Pressure-Volume Curves to Validate Assumed Specs (3rd party)





Pressure-Volume Curves to Validate Assumed Specs (3rd party)



Strength Testing

- PUC 958 requires CA operators to strength test (or replace) all pipelines without traceable, verifiable and complete records of a strength test to validate historical MAOP
- PG&E is more conservative and uses the lower of 619(a)(1)-(4)

Regulatory Oversight

- PG&E has held multiple workshops with SED and has been transparent about MAOP Validation process
- MAOP Validation process and the Procedure for Resolution of Unknown Pipeline Features (PRUPF) has been reviewed by SED (as part of PSEP safety review, report issued on ...)

Thank You

Vincent Tanguay

